The cost of boarding properties is not to be included in the maximum allowable limit per property. Mortgagees shall not board a property unless they have prior written approval from the local HUD office, or if the property is located in one of the pre-approved boarding areas listed in this attachment. The property may also be pre-approved for boarding if the property is severely fire damaged (see below). If a property is boarded without prior approval, HUD will not reimburse the mortgagee for any costs associated with the boarding. In addition, HUD will reduce the claim by any amounts that must be expended to remove boards or repair damage caused by unauthorized boarding.

When a property is boarded with prior approval, there should be no boarding above the first floor unless the opening is accessible. Accessible means that: 1) entry is possible <u>without</u> the use of a ladder; and 2) the opening is large enough for a person to easily pass through. Openings above the first floor which do not meet <u>both</u> of these tests should <u>not</u> be boarded unless otherwise specified in this attachment. If security bars are located on windows/doors, boarding is not required.

Third story or higher openings are rarely accessible and therefore shall not be boarded. Second story openings are typically accessible only from attached properties with connecting porch roofs. In the absence of such conditions, second story or higher openings shall not be boarded but must be secured to prevent unauthorized entry and to protect against weather damage. Further, openings too small for a person to pass through, regardless of location, should be secured but not boarded, unless otherwise specified in this attachment.

For the purpose of this document, the definition of united inch (u.i) is length plus width.

Specific boarding instructions and diagrams are provided on pages 22 through 31 of this attachment. See the cost schedule for the appropriate local HUD office to determine the requirements particular to the property being secured. If no requirements are provided in this document for the for the property being boarded, use local codes.

Severely Fire Damaged and Possible Demolition Properties

Properties which have suffered severe fire damage will need to be secured for safety reasons and to prevent unauthorized entry. All first floor windows and doors and all basement windows and doors will have 3/8" plywood covering the entire opening and frame. Covering must be nailed or screwed directly to the structure without 2 x 4 bracing. Trash and debris should not be removed from the interior of the property unless required by local code.

The additional costs of securing a severely fire damaged property are not included in the boarding cost limit or the maximum limit per property. However, mortgagees must request prior written approval from the local HUD office if the cost of securing a severely fire damaged property will exceed \$450.

New England Offices

Local HUD Office(s)	Variation(s) From General Requirements	Service	Cost
Connecticut State	Boarding pre-approved for the cities of:	Small window (up to 5 ft.)	\$38
		Large window (over 5 sq. ft.)	\$45
	Bridgeport New Haven	Front door	\$ 60
		Double door	\$ 75
		Sliding glass door	\$ 90
		Garage door	\$98
		Double garage door	\$130
Massachusetts State	Boarding pre-approved for the following zip code areas:	Small window (≤ 54 u.i.)	\$40
	Boston	Large window (> 54 u.i.)	\$50
	02108, 02109, 02110, 02118, 02119, 02120, 02121, 02122, 02124, 02125,	Front door (≤ 126 u.i.)	\$70
	02126, 02127, 02128, 02130, 02131, 02136	Double door (> 126 u.i.)	\$85
		Sliding glass door	\$100
	Lawrence 01840, 01841, 01842, 01843, 01845	Garage door	\$110
	Brocton 02401, 02402	Double garage door	\$145
i i	Lynn 01902, 01903, 01904, 01905		
New Hampshire State (Includes States of Maine,		Small window (up to 5 ft.)	\$38
New Hampshire, Vermont)		Large window (over 5 sq. ft.)	\$45
		Front door	\$60
		Double door	\$75
		Sliding glass door	\$ 90
		Garage door	\$98
		Double garage door	\$130

New England Offices (continued)

Local HUD Office(s)	Variation(s) From General Requirements	Service	Cost
Rhode Island State	Boarding pre-approved for:	Small window (up to 5 ft.)	\$45
	Providence Washington Park Section	Large window (over 5 sq. ft.)	\$55
	of Cranston	Front door	\$7 0
		Double door	\$85
		Sliding glass door	\$100
		Garage door Double garage door	\$110 \$145

New York / New Jersey Offices

Local HUD Office(s)	Variation(s) From General Requirements	Service	Cost
Albany		Openings up to 5 sq. feet	\$35
		Openings over 5 sq. feet	\$55
		Front door	\$70
		Double door	\$100
		Sliding Glass Door	\$75
		Garage Door Double Garage Door	\$95 \$130
Buffalo	Emergency board-up of unsecured	Openings up to 5 sq. feet	\$35
	opening (windows, door) that are accessible or that are open to the elements do not require prior	Openings over 5 sq. feet	\$55
	written approval if the cost is less than \$250. Subsequent emergency	Front door	\$70
	board-up OR any board-up that costs in excess of \$250 requires	Double door	\$100
	prior written approval.	Sliding Glass Door	\$75
	NOTE: Emergency board ups must be supported by before and after photographs.	Garage Door Double garage door	\$95 \$130
	Broken window panes are to be replaced rather than boarded on properties that are otherwise in good repair, except properties where the mortgagee has documented evidence of repeated vandalism.		

New York / New Jersey Offices (continued)

Local HUD Office(s)	Variation(s) From General Requirements	Service	Cost
Camden	Boarding is required without prior approval in the following zip code	Openings up to 5 sq. feet	\$35
	areas:	Openings over 5 sq. feet	\$55
	08016 08102 08232 08608 08030 08103 08312 08609	Front door	\$70
	08066 08104 08360 08611 08096 08105 08401 08618	Double door	\$100
	08101 08110 08600 08629	Sliding Glass Door	\$75
	Ventnor - 08406 Vineland - 08360	Garage Door	\$95
	Bridgeton - 08302 Mellville - 08332 Pennsauken - 08110 Trenton - 08650 & 08610	Double garage door	\$130
New Jersey State	Boarding is required in the	Openings up to 5 sq. feet	\$35
	followings areas:	Openings over 5 sq. feet	\$55
	Newark, Paterson, Jersey City, East Orange, Plainfield, and Irvington	Front door	\$ 70
		Double door	\$100
		Sliding Glass Door	\$75
		Garage Door	\$ 95
¥		Double Garage Door	\$130
New York State	Board all areas in the New York jurisdiction without prior approval	Openings up to 5 sq. feet	\$35
	with the exception of Putnam, Rockland, and Dutchess Counties.	Openings over 5 sq. feet	\$65
	and Date and	Front door	\$155
		Double door	\$160
		Sliding Glass Door	\$165
		Garage Door	\$195

Mid-Atlantic Offices

Local HUD Office(s)	Variation(s) From General	Service	Cost
Locui IIOD Office (5)	Requirements		
District of Columbia	Bolt boarding is the preferable	Bolt or nail / screw small window	\$25
Virginia State	means to maximum secure	(4'x2'6" opening)	
West Virginia State	properties. Use of nails or screws,		• • •
	including basement windows, to	Bolt med. window (4'x4' opening)	\$40
	secure boards is prohibited except	NTs it (some second suite down (AbsA)	625
	when securing casement or other	Nail/screw med. window (4'x4'	\$35
	fixed type windows. Written justification must be supplied when	opening)	
	a method other than bolt boarding	Bolt large window (4'x8' opening)	\$ 60
	is used. 1/2 inch plywood is to be		400
		Nail/screw large window (4'x8'	\$45
		opening)	
	to be pierced or overlap each other.	1	
	Use 2 ⁿ sheet rock screws every 6	Bolt front door	\$60
	inches. Boards are to be cut to fit		
	within 3/4" of the opening. Do not	Nail/screw front door	\$ 50
	overlap wood or cover side bricks.	Dala dauble deese	6120
		Bolt double doors	\$120
		Nail/screw double doors	\$ 100
Maryland State	Bolt boarding is the preferable	Bolt or nail/screw small window	\$25
	means to maximum secure	(4'x2'6" opening)	
1	properties. Use of nails or screws,		
	including basement windows, to	Bolt medium window (4'x 4'	\$40
	secure boards is prohibited except	opening)	
	when securing casement or other fixed type windows. Written	Nail/screw med. window (4'x4'	\$35
	justification must be supplied when	opening)	3 33
	a method other than bolt boarding	-F5/	
	is used. 1/2 inch plywood is to be	Bolt large window (4'x8' opening)	\$70
•	used with light holes cut in medium	}	
·	to large size boards. Boards are not	Nail/screw large window (4'x8'	\$55
	to be pierced or overlap each other.	opening)	
-	Use 2" sheet rock screws every 6	D to C . I	670
	inches. Boards are to be cut to fit	Bolt front door	\$70
	within 3/4" of the opening. Do not overlap wood or cover side bricks.	Nail/screw front door	\$55
	overlap wood of cover side offeks.	Transciew Holli door	
		Bolt double doors	\$130
L 1		Nail/screw double doors	\$110

Mid-Atlantic Offices (continued)

Local HUD	Variation(s) From General Somice	0
Office(s)	Requirements Service	Cost
Pennsylvania State	Bolt boarding is the preferable means to Bolt or nail/screw small window	\$25
	maximum secure properties. Use of nails (4'x2'6" opening)	
	or screws, including basement windows,	640
	to secure boards is prohibited except Bolt medium window (4'x 4' when securing casement or other fixed opening)	\$40
	type windows. Written justification must	
	be supplied when a method other than Nail/screw med. window (4'x4'	\$35
	bolt boarding is used. 1/2 inch plywood is opening)	
	to be used with light holes cut in	٠.
	medium to large size boards. Boards are Bolt large window (4'x8' opening)	\$60
	not to be pierced or overlap each other. Use 2" sheet rock screws every 6 inches. Nail/screw large window (4'x8')	
	Boards are to be cut to fit within 3/4" of opening)	\$45
	the opening. Do not overlap wood or	4 15
	cover side bricks. Bolt front door	\$ 60
		252
	Boarding is pre-approved in the Nail/screw front door	\$ 50
	following zip code areas, however, mortgagees must exercise judgement Bolt double doors	\$120
	before boarding properties. Only board	W120
	if property is in a high vandalism area Nail/screw double doors	\$100
	and boarding is the only reasonable	
	means to protect the security of the	
	property.	
	17509 17560 19104 19139 19153	
	17512 17563 19120 19140 19320	
	17516 17565 19121 19141 19335	
į.	17517 18101 19122 19142 19380	
, 1	17518 18102 19124 19143 19401 17527 18103 19145 19464	
	17527 18103 19126 19145 19464 17532 18115 19131 19146	1
	17536 18117 19132 19147	
-	17547 19013 19133 19148	
	17550 19023 19138 19151	

Mid-Atlantic Offices (continued)

Local HUD Office(s)	Variation(s) From General Requirements	Service	Cost
Pittsburgh		Bolt or nail/screw small window (4' X 2'6" opening)	\$25
	to secure boards is prohibited except when securing casement or other fixed type windows. Written justification must	Bolt medium window (4' x4' opening	\$40
	be supplied when a method other than bolt boarding is used. 1/2 inch plywood is to be used with light holes cut in	Nail/screw medium window (4' x 4' opening)	\$35
	medium to large size boards. Boards are not to be pierced or overlap each other.	Bolt large window (4' x 6' opening)	\$ 60
	Use 2" sheet rock screws every 6 inches.	Nail/screw large window 4'x8' opening	\$45
	cover side bricks.	Bolt front door	\$ 60
		Nail/screw front door	\$50
		Bolt double doors	\$12 0
		Nail/screw double doors	\$100

Southeast / Caribbean Offices

Local HUD Office(s)	Variation(s) From General Requirements	Service	Cost
Alabama State	Only one trip charge may be made regardless of the number of	Boarding (1/2 inch plywood)	\$.50 / u.i.
	windows.	Boarding (5/8 inch plywood)	\$.54 / u.i.
	Exterior surface and edges of all plywood must be painted with one	Boarding (3/4 inch plywood)	\$.58 / u.i.
	coat white primer and one coat white finish. Face nailing of panels	Trip charge	\$10
	to wood frame windows is prohibited. Follow Instructions on Page 19 of 26.	(Note: United Inch (u.i.) is defined as length plus width.)	

Southeast / Caribbean Offices (continued)

Local HUD Office(s)	Variation(s) From General Requirements	Service	Cost
Caribbean	Exterior surface and edges of all	Boarding (1/2 inch plywood)	\$.42 / u. i.
Georgia State	plywood must be painted with one		ا ا
Jacksonville	coat white primer and one coat	Boarding (5/8 inch plywood)	\$.44 / u.i.
Kentucky State	white finish. Face nailing of panels		
Knoxville	to wood frame windows is	Boarding (3/4 inch plywood)	\$.46 / u.i.
Memphis	prohibited.		i
Mississippi State		(Note: United Inch (u.i.) is	
North Carolina State		defined as length plus width.)	
Orlando			
South Carolina State			1
Tennessee State			
Coral Gables	Boarding is pre-approved in the	Boarding (1/2 inch plywood)	S.42 / u.i.
Tampa	following zip code areas:		
	Ì	Boarding (5/8 inch plywood)	\$.44 / u.i.
	Coral Gables: 33004, 33009, 33010,		
1	33012, 33013, 33014, 33020, 33023,	Boarding (3/4 inch plywood)	\$.46 / u.i.
	33034, 33054, 33055, 33056, 33060,		
	33069, 33122, 33125, 33127, 33128,	(Note: United Inch (u.i) is] !
1	33130, 33131, 33132, 33136, 33137,	defined as length plus width.)	l i
	33138, 33142, 33147, 33150, 33157,		
N .	33161, 33167, 33168, 33169, 33170,	Į.	
	33177, 33181, 33190, 33311, 33315,		1
	33316, 33401, 33403, 33404, 33405,		
	33407, 33426 (east of I-95), 33435,		<u> </u>
	33441, 33444, 33460, and 33462		
	(east of I-95).		
	Tampa: 33603, 33604, 33605, 33610,		
	1 •	1	
	33705, 33707, 33711, and 33712.		
¥.	Exterior surface and edges of all		
. *	plywood must be painted with one	·	
	coat white primer and one coat		
	white finish. Face nailing of panels		
·	to wood frame windows is		
	prohibited.		

Midwest Offices

Local HUD Office(s)	Variation(s) From General Requirements	Service	Cost
Cincinnati Indiana State Ohio State	Unless extenuating site conditions or neighborhoods justify installation of plywood boarding, securing	Bolt board windows Nail board windows	\$.30 / u.i. \$.25 / u.i.
	contractor shall confine installation to wire meshing windows. See pages 22 and 23 of this attachment for specific instructions and diagrams.	Screening (Note: United Inch (u.i.) is defined as length plus width.)	\$.25 / u.i.
Cleveland	Cloth screening is allowed, where needed, without prior approval in all urban areas. See page 23 of this attachment for specific instructions and diagram.	Screening (Note: United Inch (u.i.) is defined as length plus width.)	\$.25 / u.i.
Flint	Do not screen. Do not replace broken glass. Cover all broken glass areas by nail boarding openings. First floor openings are the only areas to be considered for boarding. Any additional boarding must be approved by the Flint office.	Nail board windows (Note: United Inch (u.i.) is defined as length plus width.)	\$.25 / u.i.
Grand Rapids	Do not replace broken glass. Cover all openings exposed to the elements with visqueen. See page 23 of this attachment for specific instructions and diagram.	Cover opening w/ Visqueen	\$5 per opening
Illinois State	Install cloth screening - cloth screen first floor openings in zip codes 60608, 60609, 60610, 60612, 60615, 60616, 60617, 60619, 60620, 60085, 60621, 60622, 60623, 60624, 60627, 60628, 60636, 60637, 60643, 60429, 60644, 60649, 60651, 60653, 60426, 60411, 60466, 60477, 60443. Screening of wood windows is accomplished by framing the window with 2x2's. The screening is stapled over the frame and fastened with 1x2 furring laths. See page 23 of this attachment for specific instructions and diagram.	(Note: United Inch (u.i.) is defined as length plus width.)	\$.36 / u.i.

Midwest Offices (continued)

Local HUD Office(s)	Variation(s) From General Requirements	Service	Cost
Michigan State	In all areas, do not replace broken glass; nail board openings where glass is broken with prior approval.	Nail board windows (Note: United Inch (u.i.) is defined as length plus width.	\$.25 / u.i.
Minnesota State	See page 22 of this attachment for specific instructions and diagrams.	Bolt board door	\$65 per opening
	Board door openings when door is missing and security cannot otherwise be established.	Nail board windows	\$20 per opening
		Bolt / nail small window	\$10/pane
Wisconsin State	Screening is the required method of securing property, however,	Screening windows	\$.25 / u.i.
	boarding is permitted if windows are broken. Follow the general	Bolt boarding windows	\$.30 / u.i.
	procedures on page 23 of this attachment, but also include the use of 2 x 4's around the perimeter of each window opening (between the	Nail boarding windows	\$20/ opening
	window and the screen material). Bolt boarding is permitted if there is no wood trim. Second and third floor openings may be boarded if broken to protect the property from outside elements. Secure boards to exterior of property. Screening areas are Milwaukee-Area bounded by Capitol Drive on the north, Humbolt Avenue on the east,	(Note: United Inch (u.i.) is defined as length plus width.)	
\$	Interstate I-94 on the south, and Sherman Blvd. on the west.		

Southwest Offices

Local HUD Office(s)	Variation(s) From General Requirements	Service	Cost
Arkansas State	Use 3/8 inch or greater by 9-inch or		\$20
Lubbock	10-inch carriage bolt mated with nut		
Houston		Medium windows (30 x 42 in.)	\$25
Louisiana State	holes in 2 by 4 stock and plywood		
San Antonio		Large windows (36 x 60 in.)	\$30
Texas State	openings to be of sufficient size to	Sametra Dana	620
	fully accept square portion of bolt beneath head. Bolt and mated	Security Door	\$30
	1	Front Door	\$35
	plated. Bolts must be tightened to	l Tont Bool	ردو
	maximum extent without disturbing	Garage Door	\$80
	wood materials. See diagrams on		
	pages 24 through 26 for further	Sliding Glass Door	\$50
	instruction.		·
		Double Door	\$70
Į.	1: Size and location of openings		:
	must be specified on the request to	Attic opening (Scuttle hole)	\$15
	HUD for approval to board.		
	2: All fabricated boards will be		
	plainly marked on the inside surface		
	with the exterior dimensions to the		
	nearest 1/8 inch to facilitate		
1	interchangability. 3: All fabricated boards will be		
	painted with one coat of primer on		
1	exterior surface and edges.		
	4: A 3-inch minimum opening		
	should be left at the tops of		
	boarded windows for light.		
	5: To ensure no hazards exists,		
•	remove all broken glass from the		
	windows, as well as the interior and		
1	exterior surrounding areas.		
	6: Use the 1/2 inch or 3/4 inch		
	plywood where plywood is required.		

Southwest Offices (continued)

Local HUD Office(s)	Variation(s) From General Requirements	Service	Cost
Oklahoma State	Use 3/8 inch or greater by 9-inch or	Small windows (24 x 36 in.)	\$30
		Medium windows (30 x 42 in.)	\$40
		Large windows (36 x 60 in.)	\$ 50
	openings to be of sufficient size to fully accept square portion of bolt	Security Door	\$50
	beneath head. Bolt and mated hardware may be galvanized or cad plated. Bolts must be tightened to	Front Door	\$50
	maximum extent without disturbing	Garage Door	\$100
	wood materials. See diagrams on pages 24 through 26 for further instruction.	Sliding Glass Door	\$80
		Double Door	\$80
	1: Size and location of openings must be specified on the request to HUD for approval to board. 2: All fabricated boards will be	Attic opening (Scuttle hole)	\$30
	plainly marked on the inside surface with the exterior dimensions to the nearest 1/8 inch to facilitate		
	interchangability.		
	3: All fabricated boards will be		
	painted with one coat of primer on exterior surface and edges.		
	4: A 3-inch minimum opening		
	should be left at the tops of		
	boarded windows for light. 5: To ensure no hazards exists,		
i i	remove all broken glass from the		
, * •	windows, as well as the interior and		
	exterior surrounding areas.		
	6: Use the 1/2 inch or 3/4 inch plywood where plywood is required.		

Southwest Offices (continued)

Local HUD Office(s)	Variation(s) From General	Service	Cost
	Requirements		
New Mexico State	Use 3/8 inch or greater by 9-inch or	Small windows (24 x 36 in.)	\$25
	10-inch carriage bolt mated with nut		
	and 2 1- inch flat washers. Drill	Medium windows (30 x 42 in.)	\$30
	holes in 2 by 4 stock and plywood		İ
	to be 3/8 inch in diameter. Washer	Large windows (36 x 60 in.)	\$35
	openings to be of sufficient size to		
	fully accept square portion of bolt	Security Door	\$35
	beneath head. Bolt and mated		
	hardware may be galvanized or cad	Front Door	\$40
	plated. Bolts must be tightened to		
	maximum extent without disturbing	Garage Door	\$90
	wood materials. See diagrams on		
	pages 24 through 26 for further	Sliding Glass Door	\$60
	instruction.		
		Double Door	\$80
	1: Size and location of openings		
	must be specified on the request to	Attic opening (Scuttle hole)	\$15
	HUD for approval to board.	, , , ,	
	2: All fabricated boards will be		
	plainly marked on the inside surface		
	with the exterior dimensions to the		
	nearest 1/8 inch to facilitate		
	interchangability.		
<u> </u>	3: All fabricated boards will be		1
]	painted with one coat of primer on		1
	exterior surface and edges.	1	
	4: A 3-inch minimum opening		
	should be left at the tops of		
	boarded windows for light.		
	5: To ensure no hazards exists,		
Ĭ.	remove all broken glass from the		
, *	windows, as well as the interior and		
	exterior surrounding areas.		
	6: Use the 1/2 inch or 3/4 inch		
-	plywood where plywood is required.		
	1,		<u> </u>

Southwest Offices (continued)

Local HUD	Variation(s) From General	Service	Cost
Office(s)	Requirements		
Shreveport	See page 27 of this attachment for specific boarding instructions and diagram.	Small windows (24 x 36 in.)	\$25
	1	Medium windows (30 x 42 in.)	\$30
	·	Large windows (36 x 60 in.)	\$35
		Security Door	\$35
		Front Door	\$ 40
		Garage Door	\$90
		Sliding Glass Door	\$60
		Double Door	\$80
		Attic opening (Scuttle hole)	\$ 15
Tulsa	Use 3/8 inch or greater by 9-inch or 10-inch	Small windows (24 x 36 in.)	\$40
	carriage bolt mated with nut and 2 1- inch flat washers. Drill holes in 2 by 4 stock and plywood to be 3/8 inch in diameter. Washer openings to be of	Medium windows (30 x 42 in.)	\$50
	1	Large windows (36 x 60 in.)	\$ 60
	galvanized or cad plated. Bolts must be tightened to maximum extent without disturbing wood	Security Door	\$ 60
,	materials. See diagrams on pages 23 through 26 for further instruction.	Front Door	\$7 0
	1: Size and location of openings must be specified	Garage Door	\$160
	on the request to HUD for approval to board. 2: All fabricated boards will be plainly marked on	Sliding Glass Door	\$100
	the inside surface with the exterior dimensions to the nearest 1/8 inch to facilitate interchangability.	Double Door	\$14 0
	 3: All fabricated boards will be painted with one coat of primer on exterior surface and edges. 4: A 3-inch minimum opening should be left at the 	Attic opening (Scuttle hole)	\$30
	tops of boarded windows for light. 5: To ensure no hazards exists, remove all broken		
	glass from the windows, as well as the interior and		
	exterior surrounding areas. 6: Use the 1/2 inch or 3/4 inch plywood where		1
	plywood is required.		

Great Plains Offices

Local HUD Office(s)	Variation(s) From General Requirements	Service	Cost
Iowa State	1/2 inch plywood, cut to fit opening, painted on exterior side, nail / bolt	Small windows (basements)	\$.30 / u.i.
		Medium windows	\$.30 / u.i.
	When there is no primary entry door, install security door.	Large windows (picture)	\$.35 / u.i.
	Construct door for main entrance (5/8 plywood) with hasp/padlock and	Casement window - single	\$.30 / u.i.
	hinge. Paint exterior side.	Front door	\$.22 / u.i.
		Double door	\$.22 / u.i.
-		Sliding glass door	\$.22 / u.i.
		Garage door	\$.15 / u.i.
		Security door	\$.22 / u.i.
		Block 1 door w/2x4	\$10/ opening
		(Note: United Inch (u.i.) is defined as length plus width.)	
Kansas/Missouri State	1/2 inch plywood, cut to fit opening, painted on exterior side, nail / bolt	Small windows (basements)	\$15
	boarding per opening.	Medium windows	\$25
	When there is no primary entry door, install security door.	Large windows (picture)	\$35
i	Construct door for main entrance (5/8 plywood) with hasp/padlock and	Casement window - single	\$15
, •	hinge. Paint exterior side.	Front door	\$25
		Double door	\$50
		Sliding glass door	\$50
		Garage door	\$50
		Security door	\$50
		Block 1 door w/2x4	\$10

Great Plains Offices (continued)

Local HUD Office(s)	Variation(s) From General Requirements	Service	Cost
Nebraska State	1/2 inch plywood, cut to fit opening,	Small windows (basements)	\$ 15
St. Louis	painted on exterior side, nail / bolt boarding per opening.	Medium windows	\$25
	When there is no primary entry door, install security door.	Large windows (picture)	\$35
	Construct door for main entrance (5/8 plywood) with hasp/padlock and	Casement window - single	\$25
	hinge. Paint exterior side.	Front door	\$25
		Double door	\$50
		Sliding glass door	\$50
		Garage door	\$50
		Security door	\$60
		Block 1 door w/2x4	\$10

Rocky Mountain Offices

Local HUD Office(s)	Variation(s) From General Requirements	Service	Cost	
Colorado State (Includes States of Colorado, South Dakota, Wyoming)	If a swamp cooler is removed, board the opening without authorization from HUD to prevent interior damage. Emergency boarding and securing should be telephoned into the Colorado State Office and a verbal response will be given immediately. Mortgagees must follow up with a written request confirming the verbal authorization via fax.	Boarding	\$2/ sq. ft.	
Montana State North Dakota State Utah State	If a swamp cooler is removed, board the opening without authorization from HUD to prevent interior damage.	Boarding	\$2/ sq. ft.	

Pacific | Hawaii Offices

Local HUD Office(s)	Variation(s) From General Requirements	Service	Cost
Arizona State	Boarding is pre-approved in the	Small windows (less than 8 sq ft)	\$35
	All properties located on Indian Reservations and an area located in	Medium windows (8-16 sq ft)	\$50
	South Phoenix "Beginning at the intersection of 51st Avenue and	Large windows (16-32 sq ft)	\$65
	Washington Street, thence Southerly along 51st Avenue to Ray Road,	Slider (over 32 sq ft)	\$80
	thence Easterly to the boundary line of South Mountain Park, thence along the Northern boundary line of South Mountain Park to 40th Street, thence Northerly along 40th Street to Washington Street, thence Westerly to the point of beginning.	(Where there is no primary	\$130
	See pages 28 and 29 of this attachment for specific boarding instructions and diagram.		
California State	See page 28 and 29 of this attachment for specific boarding instructions and diagram.	Small window (less than 8 sq. ft)	\$35
	If window frames are badly damaged	Medium windows (8-16 sq. feet)	\$ 50
	or missing, the window(s) are to be boarded without prior approval.	Large windows (16-32 sq. feet)	\$65
	Unusual openings such as a doggy-door, or where a wall air-	Slider (over 32 sq. feet)	\$ 85
	conditioner or cooler was once installed, must be secured, usually by boarding. Prior approval is not required to board these. A before and after picture is required.	Security door w/ padlock (Where there is no primary door, install security door.)	\$130
·	Contact the local HUD office for boarding instructions when conveying properties in the following cities: Pittsburgh, San Pablo, Oakland, Richmond, and Vallejo.		

Pacific | Hawaii Offices (continued)

Local HUD	Variati	on(s) From	General	Service	C4
Office(s)		Requirement.		Service	Cost
Fresno		d 29 of this attac	chment for	Small windows (less than 8 sq ft)	\$40
		•		Medium windows (8-16 sq. feet)	\$55
				Large windows (16-32 sq. feet)	\$7 5
				Slider (over 32 sq. feet)	\$ 90
				Security door w/ padlock (Where there is no primary door, install security door.)	\$130
Hawaii State Nevada State Reno		d 29 of this atta g instructions an		Small window (less than 8 sq. ft)	\$35
Santa Ana Tucson				Medium windows (8-16 sq. feet)	\$50
				Large windows (16-32 sq. feet)	\$65
				Slider (over 32 sq. feet)	\$80
				Security door w/ padlock (Where there is no primary door, install security door.)	\$130
Los Angeles		n the jurisdiction located in the fo		Small window (less than 8 sq ft)	\$35
	only, must be se		low screens (not	Medium windows (8-16 sq. feet)	\$ 50
*		arding. See spec		Large windows (16-32 sq. feet)	\$65
, 51				Slider (over 32 sq. feet)	\$80
	Inglewood Pasadena Compton	Los Angeles San Fernando Azusa	Pacoima Pomona Long Beach	Security door w/ padlock (Where there is no primary door, install security door.)	\$130
	Pico Rivera La Puenta	Lynwood Carson	W. Covina Wilmington	Back or side door	\$80
	Hawaiian Gardens	Huntington Park	Duarte South Gate		
	Paramount	Artesia	Whitter		
	Harbor City Bellflower	Downey	Hacienda Heights		

Pacific | Hawaii Offices (continued)


Local HUD	Variation(s) From General	Service	Cost
Office(s)	Requirements	30,,500	000
Sacramento	areas:	Small windows (less than 8 sq ft)	\$50
	Hayfork 96041, Olivehurst 95961, Broderick 95065, Anderson 96007, Maryville 95901, Rio Lind 95673 & 95676,	Medium windows (8-16 sq ft)	\$65
	Del Paso 95838, Oak Park 95817, Florin Rd. 95823	Large windows (16-32 sq ft)	\$80
		Slider (over 32 sq ft)	\$ 95
	Board all broken windows in any area; also, board broken windows when receive a police report.	Security door w/ padlock (Where there is no primary door, install security door.)	\$130
	See pages 28 and 29 of this attachment for specific boarding instructions and diagram.	,	
San Diego	Boarding is pre-approved in the following areas: 1. The area in the City of San Diego	Small windows (less than 8 sq ft)	\$35
		Medium windows (8-16 sq. feet)	\$50
	2. The area in the city of San Diego south of University and between 34th Street &	Large windows (16-32 sq. feet)	\$ 65
	Euclid. 3. The area in the county of San Diego	Slider (over 32 sq. feet)	\$80
	south of Highway 94 and north of Paradise Valley Road and Highway 54. 4. Oceanside 92057, Calle Mariposa, Calle	Security door w/ padlock (Where there is no primary door, install security door.)	\$130
	Estrella, Calle Solimar, Calle Vallecito, Calle Los Santos, and Calle Las Positas.	door, mstan security door.)	
i i	92054 Debuque St., Lemon St., Higgins St. Pula St.??, Bush St.,?? Buena St., Olive		
, •	St., Santa Barbara St., and San Diego St. City of VistaBoundaries: Bobier "North"		
_	Vista Way "East & South and N. Melrose "West"		
	City of Escondido Boundaries: 2nd St. "North" 15th St., "South", Upas St., "West",		
	Juniper "East" Grand "North", 5th "South", Ash "East" and Juniper "West"		
	"DO NOT BOARD CONDOS" 5. All Imperial County When in doubt call the local HUD office		
	See pages 28 and 29 of this attachment for specific boarding instructions and diagram.		

Northwest | Alaska Offices

Local HUD Office(s)	Variation(s) From General Requirements	Service	Cost
Alaska State	No pre-approved boarding		ı
Idaho State	areas. Prior written approval		
Oregon State	required.		
Washington State			

PLYWOOD BOARDING INSTRUCTIONS FOR MIDWEST OFFICES


AND ALABAMA STATE OFFICE




This illustration graphically identifies the method of installing plywood in window openings. Unless extenuating site conditions or neighborhoods justify this type of installation, securing contractor shall confine installation to wire meshing windows.

These instructions are to be followed for boarding doors and windows in Alabama.


SCREENING INSTRUCTIONS FOR MIDWEST OFFICES




SECURING INSTRUCTIONS FOR SOUTHWEST OFFICES




SECURING INSTRUCTIONS FOR SOUTHWEST OFFICES



SECURING INSTRUCTIONS FOR SOUTHWEST OFFICES






All boarding in the Shreveport Office jurisdiction must meet these specifications

BOARDING INSTRUCTIONS FOR PACIFIC / HAWAII OFFICES


Maximum Security Specifications



All windows and doors shall be secured. All openings except the front door shall be secured per the above drawing, or similar, as conditions permit with one piece of plywood only, unless the opening requires larger than a 4′ X 8′ sheet. All plywood shall be 5/8" except the Security Door which shall be 3/4". Remove all removable glazed sections where glass is intact and place inside the house. Openings 30" high or less may be secured with only one 2 X 4 and two bolts. All bolts securing the 2 X 4′s must be tightened carefully to be snug, but not crush the interior finishes. The purpose of the double nuts is to tighten them against one another as tight as possible. If the dwelling has decorative item adjacent to the opening, such as surface applied shutters, etc., that are easily removed, carefully remove them and place inside the house.

BOARDING INSTRUCTIONS FOR PACIFIC / HAWAII OFFICES (CONTINUED)

Front door detail



Set plywood flush with brick mould on hinge side.

Lap plywood over brick mould on lock side.

Fit edges as close as practical.

The Security Door which shall be 3/4" plywood.

Hinges shall be 6" Extra Heavy Tee.

The locking device shall be an 8" X 12" flat tee strap with a five pin, 3/8 inch hardened steel shackle padlock (padlock not included in price of door).

The front door shall be secured as per the "front door detail" for either masonry or frame exterior walls. The tee portion of the hinge shall be fastened with 1 1/2 screws to the jamb. Pilot holes must be drilled so as to not split the jamb. The tee strap shall be nailed through the door stop and jamb with 6d box nails. Cut a slot in the plywood just large enough for the strap leg and reinforce both outer edges of the slot with flat straps (minimum 1" x 8") fastened with carriage bolts. If the door jamb is loose and has applied stop, remove the stop and renail the jamb with 16d cut or box nails as appropriate, located so that the new stop will cover the nails.

Attic access panels in the carport ceilings shall be secured by nailing a piece of plywood into the joists only, with a minimum of four 16d box or common nails (maximum charge \$15.00). "Carport" type storage rooms which are not part of the main house shall be secured by nailing one piece of plywood to the jamb, over the door (maximum charge \$30.00).

Exact boarding specifications may vary among the local offices. Specifications can be obtained from the Chief Property Officers.

SECURITY SCREEN INSTRUCTIONS FOR LOS ANGELES OFFICE

BAMPLE SPECIFICATION

I. SCREEN MODULE COMPONENTS -

MATERIAL DESCRIPTION

(a). FRAME ELEMENT:

15/16" >: 7/16" x .060" wall thick, 6063-T5 aluminum alloy extrusion.

(Frame element has inherent locking feature that mechanically locks the . security grille in place when assembled.)

(b) EECURITY GRILLE: Plastic coasted 1-1/2" x 3 diamond pattern 13 ga. and flattened carbon steel, (color grey) (Electrostatically coated vinyl powder that is temperature fused to form a. · thin film protective coating.)

(c) IMPER COUNTRY!

(d). SPLINE:

(c) ECREEM:

.100" thick 6061-T6 aluminum alloy.

..185" vinyl, serrated.

18/14 alclad aluminum screening.

II. ATTACH HARDAYARE

(a) RESTRAINT BRACKET

(b) CHARREL BRACKET

(c) CLEVIS FIN

(d) UÇİCK RELEASE FULL PIN


MATERIAL DESCRIPTION

.062 thick 6061-T aluminum alloy (See Fig. 1).

.062 thick 6061-T aluminum allay (See Fig. II).

1/4" dia. x reqd. length, cadmium plated steel.
.060 dia, piano wire cadmium plated steel.


III. CUICK RELFASE PIN TYPES



SECURITY SCREEN INSTRUCTIONS FOR LOS ANGELES OFFICE

IY. INSTALLATION

(a). DOUBLE HUNG WENDOWS:



- (b). ALUMINUM SLIEER WINDOWS: SECURITY SCREENS covering fixed windows are surface mounted and attached with tamper proof fasteners, est 6 inches from each corner and 18 inches on center along each side. There shall be a minimum of 2 fasteners per each side. SECURITY SCREENS covering sliding windows are surface mounted and secured with clevis and quick release pins that are accessible from the inside when the window is opened.
- (c). CASEMENT WINDOWS: SECURITY SCREENS covering fixed and pivet windows are anchored to the existing window sash/frames with tamper proof fasteners, set 6 inches from each corner and 18 inches on center along each side. There shall be a minimum of 2 fasteners per each side. Where possible, the pivot window screen should be sized for cutdoor/indoor convertibility, i.e., after occupancy, the screen can be insuffed on the inside.

